# Mudroom Laundry Measurement Sheet

## Map out your exact cabinet, hook, and appliance placements for comfortable daily use.

Ensure your bench and aisles are properly sized for the chaos of daily traffic. Verify these crucial spatial allowances before you finalize your cabinetry order.



### Crucial Spatial Allowances

**18 in**
Bench seat height for daily traffic

**40 in**
Kid hooks inside lockers for independence

**65 in**
Adult hook height for winter coats

**Min. 8 in**
Shoe cubby height for bulky boots

**Min. 12 in**
Vertical clearance above the boot tray

**Min. 72 in**
Upper cubbies for clean, dry gear

**Min. 36 in**
Drying rod over sink for drips

**Min. 1 in**
Side clearance for stacked laundry machines

*Space Hooks for Winter Coats*

*Measure your thickest winter jacket and add four inches. Mark your hook centers using that total dimension so damp outerwear can dry efficiently overnight without bunching.*

## Select Durable Surface Finishes

Find your row: **Your surface zone**

| Your surface zone | Your pick | Why |
|---|---|---|
| **Locker interiors and bench seats** | Catalyzed conversion varnish | Resists chips from heavy backpacks |
| **Inner shoe shelves and trays** | High-pressure laminate | Maximum durability for wet, muddy footwear |
| **Upper cubbies and ceiling trim** | Standard latex paint | Moderate durability for clean, dry items |
| **Wall behind utility sink** | Non-porous backsplash material | Stops muddy splashes from staining drywall |

## Plan Your Layout On Site

- [ ] Verify a 42-inch minimum clear space for aisles and laundry doors.
- [ ] Map out a 20-inch bench depth to prevent winter morning bottlenecks.
- [ ] Plan deep lower drawers for breathing cane-front hamper bins holding canvas bags.
- [ ] Size the heated tile boot dock slightly beyond footwear to evaporate snow.
- [ ] Check glide packaging for the toe-kick step for tots' safe weight rating.
- [ ] Ensure your 24-inch sink cabinet fits a 10-inch deep basin and sprayer.

## Project Notes

Enjoy your beautifully organized, hard-working entryway!